

**AIP SUPPLEMENT  
(SUP)****H19/25****Effective: 202501301600 UTC**

AERONAUTICAL INFORMATION SERVICE,  
AIRSERVICES AUSTRALIA, GPO BOX 367,  
CANBERRA ACT 2601

For **DISTRIBUTION** queries, contact:  
Email: [aim.editorial@airservicesaustralia.com](mailto:aim.editorial@airservicesaustralia.com)

For **CONTENT** queries regarding this SUP, contact:  
Email: [edn.baso@defence.gov.au](mailto:edn.baso@defence.gov.au)

# **RAAF BASE EDINBURGH AERODROME (YPED) TOW-WAY CONSTRUCTION STAGE 2 - RWY 18 DTHR**

## **1. INTRODUCTION**

- 1.1 This AIP SUP cancels and replaces SUP H17/25 with changes to para 3. The SUP provides notification and operational information to aircraft and ground operations in regard to the displaced THR (DTHR) RWY 18.
- 1.2 Works are underway to construct a tow-way connecting RWY 18/36 to the Deep Maintenance Modification Facility (DMMF) which is being constructed to the north-east of the runway.
- 1.3 The DTHR RWY 18 is required to facilitate the construction of the tow-way by providing obstacle limitation surface clearance for construction equipment operation up to nine metres above ground level within the RWS and providing a sufficient safety distance behind departing and arriving aircraft to prevent harm to workers and equipment.
- 1.4 The construction works include excavation, pavement construction, and aeronautical ground lighting changes/additions.
- 1.5 All works affecting aircraft operations, including displacement preparation works, will be advised via the distribution of a Method of Working Plan.
- 1.6 The actual date and time of works will be advised by NOTAM.

## 2. WORK PROGRAMME

2.1 Stage 2 - THR RWY 18 displacement 31 January 2025 to May 2025.

2.1.1 Northern end RWY 18/36

- a) THR RWY 18 DTHR of 287M (942FT) will remain in place for the entire period referenced under this SUP
- b) DTHR RWY 18 will comprise of temporary lighting with the current THR RWY 18 lighting extinguished
- c) RWY 18 PAPI will be extinguished and replaced with a single set of four PAPI units on the left side of RWY 18
- d) RTIL will be installed at RWY 18 DTHR
- e) Touchdown indicators will be marked by painted lines both sides of the RWY 150M and 450M from DTHR
- f) HIRL within the displacement length will be extinguished
- g) RWY 18 HIAL and SFAL will be extinguished
- h) RWY 18/36 DTRM within the displacement will be extinguished and covered
- i) RWY 36 DTRM will be adjusted to the correct distances
- j) DTHR RWY 18 will include new line marking, threshold arrows and RWY designator. The current THR RWY 18 line marking will be covered
- k) Northern aircraft arrestor system is unavailable
- l) RWY 18 ILS GP unavailable during displacement period

### 3. RUNWAY DISTANCE SUPPLEMENT

| RWY | TORA        | TODA                | ASDA        | LDA         |
|-----|-------------|---------------------|-------------|-------------|
| 18  | 2586 (8484) | 2646 (8681) (2.77%) | 2586 (8484) | 2273 (7457) |
| 36  | 2642 (8668) | 2702 (8865) (7.37%) | 2642 (8668) | 2526 (8287) |

#### SUPPLEMENTARY TAKEOFF DISTANCES

RWY18- 2548 (8360) (1.6%) 2584 (8478) (1.9%) 2611 (8566) (2.2%)  
2632 (8635) (2.5%)

RWY 36- 2222 (7290) (1.6%) 2323 (7621) (1.9%) 2395 (7858) (2.2%)  
2449 (8035) (2.5%) 2562 (8405) (3.3%) 2642 (8666) (5.0%)

#### TAXIWAY INTERSECTION DECLARED DISTANCES

RWY 18- TKOF from TWY E; RWY remaining 2560 (8399) reduce all DIST  
by 26 (85)

RWY 18- TKOF from TWY F; RWY remaining 1666 (5466) reduce all DIST  
by 920 (3018)

RWY 36- TKOF from TWY B; RWY remaining 2526 (8287) reduce all DIST  
by 116 (381)

RWY 36- TKOF from TWY C; RWY remaining 1866 (6122) reduce all DIST  
by 776 (2546)

### 4. CANCELLATION

4.1 This SUP cancels when Stage 2 works are complete, expected May 2025.

### 5. DISTRIBUTION

5.1 Airservices Australia website only.

#### Appendices

1. Scope of Works Image
2. Displaced Threshold Diagram

1. Scope of Works Image



## 2. Displaced Threshold Diagram

